



Copyright © 2006 by John Wiley & Sons, Inc. All rights reserved.

























## Introduction

- The normal distribution is defined by its mean value  $\bar{x}$  (i.e., in this case the value of the longest path through the net work) and the value,  $\sigma$ , which is so-called "standard deviation" of the distribution.
- The standard deviation of the distribution is a measure of how widely about the mean value the actual observed values are spread or distributed.

Construction Management, 3/E by Daniel W. Halpin Copyright © 2006 by John Wiley & Sons, Inc. All rights reserved.













Activity	t <sub>m</sub>	t <sub>a</sub>	t <sub>b</sub>	t <sub>e</sub>	Var
1	3	1	5	3	0.44
2	6	3	9	6	1.00
3	13	10	19	13.5	2.25
4	9	3	12	8.5	2.25
5	3	1	8	3.5	1.36
6	9	8	16	10	1.23
7	7	4	13	7.5	2.25
8	6	3	9	6	1.00
9	3	1	8	3.5	1.36

## Table 8.1 (p. 131)

Three Estimate Values and Calculated Values for Each Activity

 $\label{eq:Construction Management, 3/E by Daniel W. Halpin Copyright © 2006 by John Wiley & Sons, Inc. All rights reserved.$ 

































Activity #	Activity	Туре	Duration (Weeks)	Followed by Act #		
10	Prefab Wall Forms	constant	2	40		
20	Excavate Cols and Walls	constant	3	50, 60, 70		
30	Let Elec and Mech Subcontract	ta, tm, tb	3, 4, 8	60, 70		
40	Deliver wall Forms	constant	4	80, 90, 100		
50	Forms, Pour & Cure Wall & Col Fig	ta, tm, tb	6, 7, 8	80, 90, 100		
60	Rough-in Plumbing	$t_a, t_m, t_b$	5, 7, 10	110		
70	Install Conduit	ta, tm tb	9, 11, 15	110		
80	Erect Wall Forms & Steel	constant	9	110		
90	Fabricate & Set Interior Column Forms	constant	6	120		
100	Erect Temporary Roof	t <sub>a</sub> , t <sub>m</sub> , t <sub>b</sub>	12, 16, 18	140		
110	Pour, Cure & Strip Walls	constant	10	130		
120	Pour, Cure & Strip Int. Walls	constant	6	140		
130	Backfill for Slab on Grade	constant	1	140		
140	Grade & Pour Floor Slab	constant	5	END		

Problem 8.1 (p. 143)

Construction Management, 3/E by Daniel W. Halpin Copyright © 2006 by John Wiley & Sons, Inc. All rights reserved.

Activity	Description	ta	tm	t <sub>b</sub>	Followed by Activity
1	Start	0	0	0	2
2	Lead Time	10	10	10	3, 4, 5
3	Move to Site	18	20	22	6
4	Obtain Pipes	20	30	100	8, 9, 10
5	Obtain Valves	18	20	70	11
6	Lay Out Pipeline	6	7	14	7
7	Dig Trench	20	25	60	8, 10
8	Prepare Valve Chambers	17	18	31	11
9	Cut Specials	7	9	17	11
10	Lay Pipes	18	20	46	12
11	Fit Valves	8	10	12	13, 14
12	Concrete Anchors	11	12	13	13, 14, 15
13	Finish Valve Chambers	8	8	8	17
14	Test Pipeline	5	6	7	16
15	Backfill	8	10	20	16
16	Clean Up	2	3	10	17
17	Leave Site	3	4	5	18
18	End				









